

**Foulger Pratt Development, Inc.
8621 Georgia Avenue**

Compacted structural fill should be placed in maximum 8-inch thick horizontal, loose lifts. Fill should be compacted to at least 95 percent of the maximum dry density per ASTM D698 (Standard Proctor), except that the top 12 inches in pavement areas should be compacted to at least 100 percent of the same standard. Soil moisture contents at the time of compaction should be within 3 percent of the soils' optimum moisture content.

Backfill placed in excavations, trenches, and other areas that large compaction equipment cannot access should be placed in maximum 6-inch thick lifts. Backfill should meet the material, placement, and compaction requirements outlined above.

Successful re-use of the excavated, on-site soils as compacted structural fill will depend on their natural moisture contents during excavation. Scarifying and drying of these soils should be anticipated to achieve the recommended compaction. Drying of these soils will likely result in some delays, and may not be possible during cooler, wetter weather. We recommend that the earthwork be performed during the warmer, drier times of the year.

6.0 FOUNDATION RECOMMENDATIONS

We based our geotechnical engineering analysis on the information developed from our subsurface exploration and soil laboratory testing, along with the project development plans, site plans, and structural loading furnished to our office. We recommend shallow spread footings for support of the proposed apartment building based on our analysis. The following sections of the report provide our detailed recommendations.

6.1 Spread Footings

The majority of the building will be at-grade and will have a lowest level at EL +345.5 and a portion of the building will extend one level below grade with a lowest level at EL +334. Based on these lowest levels, spread footings are considered suitable for support of the proposed apartment building. Deep fill was encountered along the southeast corner of the site (borings B-7 and B-8B), considering that the building in this area will be founded at about EL +334, footings will need to be lowered to natural soils. Footings should be founded on suitable natural soils consisting of the firm silt and sand of Stratum B and the disintegrated rock of Stratum C. We recommend column footings supported on these materials be designed for a net allowable soil bearing pressure of 8,000 psf and that wall footings be designed for a net allowable soil bearing pressure of 6,000 psf. This bearing pressure provides a factor of safety against general bearing capacity failure of at least 3.0. Where design loads include combinations of transient wind and/or seismic loads that result in non-uniform soil bearing pressure distribution beneath the footing, the maximum allowable soil bearing pressure in these cases may be taken as 1.33 times the net allowable soil bearing pressure given above.

The above allowable soil bearing pressures may be increased by 33 percent for wind and seismic loads when used in conjunction with load combinations defined in IBC Section 1605.3.2, Alternative Basic Load Combinations for use with allowable stress design. This increase is not applicable for other allowable stress load combinations, strength design or load and resistance factor design.

The grades at which suitable natural soils were encountered in the test borings are presented in the tables below:

**Estimated Elevation of Suitable Subgrade Soils for Footings
Designed for a Net Allowable Bearing Pressure of 8,000 psf**

| Boring Number | Proposed Lowest Level Elevation (ft) | Estimated Elevation of Suitable Subgrade Soils (ft) |
|---------------|--------------------------------------|---|
| B-1 | EL +345.5 | EL +344 |
| B-2 | | EL +344 |
| B-3 | | EL +345 |
| B-5A | | EL +339 |
| B-6 | | EL +340 |
| B-7 | EL +334 | EL +329 |
| B-8B | | EL +330 |
| B-9 | EL +345.5 | EL +340 |

**Foulger Pratt Development, Inc.
8621 Georgia Avenue**

For planning purposes, the elevation of suitable materials between borings may be considered to vary linearly between boring locations. All footing subgrades should be observed by the Geotechnical Engineer prior to placement of concrete to verify subgrade materials are as anticipated.

If unsuitable soils are encountered at the design bearing grade, these soils should be removed and replaced as recommended by the Geotechnical Engineer. Unsuitable soils should be replaced with lean concrete.

Settlements of shallow foundations supported on suitable natural soils are not expected to exceed about one (1) inch. Differential settlements between similarly loaded footings are not expected to exceed about half this value.

Column and wall footings should be at least 24 and 16 inches wide, respectively, for shear considerations. Exterior footings should be founded at least 2.5 ft below final exterior grades for frost protection. Interior footings may be founded at nominal depths below the floor slabs. Where bearing grades between adjacent footings vary, the slope between the bottom edges of adjacent footings should not be steeper than 1.5H:1V.

7.0 FLOOR SLAB RECOMMENDATIONS

The proposed floor slabs can be supported on the firm existing fill, suitable natural soils of Strata B and C or compacted structural fill. A modulus of subgrade reaction, k, of 150 kcf (87 pci) should be used in design of floor slabs.

A 4-inch crushed stone or washed gravel capillary moisture barrier should underlie floor slabs on grade. Moisture barrier material should consist of AASHTO No. 57 crushed stone. The Contractor should compact the stone in place with at least two passes of suitable vibratory compaction equipment. A 10-mil thick polyethylene liner should be installed over the crushed stone layer as a vapor barrier and to prevent concrete intrusion into the stone.

The Contractor should compact floor slab subgrades to repair any disturbance that may occur due to construction operations before placing moisture barrier materials. Since floors will be slab-on-grade, footing and utility excavations should be backfilled with compacted structural fill as defined in Section 5.0.

8.0 RETAINING STRUCTURE RECOMMENDATIONS

The proposed apartment building will partially extend below grade, and the below-grade walls will need to be designed to withstand lateral earth pressures. Recommendations for the design of these walls are presented in the following sections.

8.1 Basement Walls

Below-grade walls will need to be designed to withstand lateral earth pressures. An average equivalent fluid pressure of $50 H$ (psf), where H is the height of the wall in feet, is recommended for design of basement walls, as illustrated on Figure 3. The recommended equivalent fluid pressure assumes a horizontal backfill behind the walls. Loading from surcharges, or sloping backfill above the walls will need to be added to the equivalent fluid pressure provided above. Hydrostatic pressures are not included in our recommended lateral earth pressures, as foundation drains should be installed behind the walls. The surcharge pressure ordinate should be obtained by multiplying the surface surcharge pressure, q , by 0.42. The walls should be backfilled as recommended below. A friction factor of 0.35 may be utilized for concrete footings and subgrade soils. Basement walls should be backfilled as recommended below.

Backfill materials for walls designed considering free-draining backfill should consist of non-plastic material classifying as SP-SM, SW-SM, SP, SW, GW-GM, GP-GM, GP or GW according to ASTM D2487. This classification includes open-graded crushed stone such as AASHTO No. 57. Free-draining backfill should be placed in the zone extending from the base of the wall upwards at 45 degrees. On-site materials used for backfill should consist of material classifying ML, SC, SM, SP, SW, GP or GW according to ASTM D2487.

The Contractor should place backfill in maximum 8-inch thick loose lifts, and compact each lift to at least 95 percent of maximum dry density according to ASTM D698 (Standard Proctor). The Contractor should place crushed stone backfill in maximum 12-inch thick lifts, and compact each lift using suitable vibratory equipment. Only light hand-operated equipment should be used to compact backfill against walls. The Structural Engineer of Record should approve the size of the compaction equipment.

9.0 SUBDRAINAGE RECOMMENDATIONS

The subsurface investigation revealed groundwater about 20 ft below existing grades, or at about EL +325 in the building footprint. To account for seasonal fluctuation, we suggest a design table groundwater elevation of EL +330 be considered. Therefore, we anticipate groundwater to be about 5 ft below the proposed lowest level at EL +334. Based on the groundwater observations, subdrainage below the floor slabs will not be necessary. However, it may be prudent to add one subdrainage line along the inside of the partial basement level to collect groundwater. Subdrainage behind the below-grade walls is also recommended.

9.1 Subdrainage for Below-Grade Walls

Earth pressure recommendations provided in this report do not include hydrostatic pressure since subdrainage will be provided behind the basement walls. Subdrainage should consist of perimeter subdrains located on top of the wall footing, next to the wall. Subdrainage lines should consist of 4-inch slotted, corrugated polyethylene tubing according to ASTM F405 surrounded by at least 4 inches of filter drainage material. A drainage geotextile should wrap around the drainage material. Subdrains should drain by gravity to an outlet, sump, or storm sewer. Filter drainage material should consist of AASHTO No. 78 aggregate.

Geocomposite drainage panels consisting of Miradrain G100N or equivalent should be installed on all basement walls. Drainage panels should be placed along the entire wall face to within 1.5 ft of finished grade. The Contractor should bind the edges of the panels with drainage geotextile to limit the potential for soil intrusion into the drainage system.

Elevator pits and other portions of the structure that extend below the lowest level should be water proofed and designed to resist full hydrostatic pressure.

Figure 4 illustrates recommended subdrainage details as discussed above.

10.0 TEMPORARY EXCAVATION SUPPORT RECOMMENDATIONS

10.1 Underpinning

Depending on the proximity of the proposed apartment building to the existing adjacent structures (three-story northern office building and 11-story western office building), as well as the foundation systems of the adjacent buildings, underpinning may be required.

10.2 Excavation Support

Depending on the available space, partial or full sloping of the excavation may be possible. However, if excavation support is required, we anticipate a soldier pile and wood lagging system will be appropriate excavation support for this project. Soldier piles should not be spaced greater than 8 ft, and wood lagging should have an unfinished thickness of at least 3 inches. Soldier piles should be inserted into predrilled holes to reduce vibrations from driving, obstructions such as concrete and brick and boulders in the natural soils. The predrilled soldier-beam holes should be backfilled with lean concrete. Selection and design of the excavation support system are the responsibility of the Contractor. A licensed Professional Engineer should design the excavation support system.

Tiebacks, struts, or rakers and heel blocks may be used to resist horizontal loads acting on the excavation support system. Permits or easements may be required since tiebacks will penetrate into public and private space. Permission will also be needed to install tiebacks below the adjacent private properties. Tiebacks should be located to avoid buried structures. Rakers or struts may be needed at locations where it is not possible to install tiebacks.

Where tiebacks are used, each tieback must be tested. A detailed specification should be prepared for the installation and testing of earth tiebacks. Design and installation should be performed in accordance with the Post Tensioning Institute's *Soil and Rock Anchors* (2006). Specifications should require that proof tests be conducted on all tiebacks. Also, at least 5 percent of tiebacks installed on the project should be performance tested. Proof testing should be performed as described below for performance testing, except the maximum load for a proof test is 120 percent of design load. During proof testing, each load step should be held for 5 minutes, and the maximum test load should be held for 15 minutes. Performance testing should involve the incremental loading of the tieback. Load steps of 25, 50, 75, 100, 120 and 133 percent of the design load should be applied. Tieback deflections during loading should be measured. Each load step should be held for at least 15 minutes. The maximum test load should be held for at least 60 minutes.

We recommend that the Geotechnical Engineer be engaged for observation and testing of the tiebacks.

Excavation bracing consisting of soldier piles and lagging is a flexible system; therefore, vertical and lateral movements beyond the limits of the excavation that may cause damage to the adjacent streets, buildings, or utilities should be anticipated. The lateral and vertical movements of the excavation bracing system should be monitored. Also adjacent buildings and ground surface should be monitored for movement. Excavation subgrades should also be monitored for instability both during excavation and following completion of the excavation.

**Foulger Pratt Development, Inc.
8621 Georgia Avenue**

The design and installation of the excavation support system should be performed by a specialty Contractor who has at least 5 years of experience in the construction of this particular work. The excavation support Contractor should be required to furnish bodily injury and property damage liability insurance to adequately protect the owner, the architect and all consulting engineers on this project from claims arising from his work. The Contractor's general liability insurance policy should also name the architect, engineer and this consultant as additional insured for claims arising from this construction.

11.0 CONSTRUCTION CONSIDERATIONS

11.1 Spread Footings

The Contractor should exercise care during excavation for spread footings so that as little disturbance as possible occurs at the foundation level. The Contractor should carefully clean loose or soft soils from the bottom of the excavation before placing concrete. A Geotechnical Engineer from our firm should observe actual footing subgrades during construction to evaluate whether subgrade soils meet the requirements as recommended in this report.

Footing subgrades needing undercut may be concreted at the elevation of undercut or backfilled to the original design subgrade elevation with lean concrete. Concreting should take place the same day as excavation of footings. Subgrades should be protected from freezing if work is performed during cold weather.

11.2 Subdrainage

The Contractor should exercise care when placing and backfilling subdrainage pipe to avoid damage to the subdrainage system during installation.

11.3 Temporary Excavation Support

Drawings should be prepared by the Excavation Contractor to indicate details of the excavation sheeting. These drawings should generally be according to the design requirements outlined in Section 10.2 of this report. However, Contractors should be allowed to submit alternate designs for sheeting plans that they select. The alternate designs should be based on lateral earth pressures indicated herein, provided free draining H-pile and wood-lagging sheeting is used. The drawings should be prepared by a licensed Professional Engineer and submitted to the Structural Engineer and to our office for review.

The recommended scope of excavation sheeting has been prepared without detailed structural plans for the proposed construction or the existing structures and underground utilities on site. The detailed drawings should be prepared based on the structural drawings and/or measurements to consider these additional details.

11.4 Rock Excavation

Based on the information provided by the borings and considering a proposed lowest level at EL +334, mass rock excavation such as hoe-ramming or blasting should not be necessary to reach the lowest level. However, based on the borings, rock excavation is expected at the following elevations:

Estimated Top of Rock Elevations

| Boring Number | Estimated Elevation Where Rock Excavation Methods will be Needed (ft) |
|---------------|---|
| B-1 | EL +333 |
| B-5A | EL +332 |
| B-6 | EL +333 |
| B-8A | EL +330 |
| B-9 | EL +332 |

Variation in rock conditions should be expected since rock surface can vary considerably over relatively shortly horizontal distances at this site.

11.5 Engineering Services During Construction

The engineering recommendations provided in this report are based on the information obtained from the subsurface exploration and laboratory testing. However, conditions on the site may vary between the discrete locations observed at the time of our subsurface exploration. The nature and extent of variations between borings may not become evident until during construction.

To account for this variability, we should provide professional observation and testing of subsurface conditions revealed during construction as an extension of our engineering services. These services will also help in evaluating the Contractor's conformance with the plans and specifications. Because of our unique position to understand the intent of the geotechnical engineering recommendations, retaining Schnabel for these services will allow us to provide consistent service throughout the project construction.

12.0 GENERAL SPECIFICATION RECOMMENDATIONS

An allowance should be established to account for possible additional costs that may be required to construct earthwork and foundations as recommended in this report. Additional costs may be incurred for a variety of reasons including variation of soil between borings, greater than anticipated unsuitable soils, need for borrow fill material, wet on-site soils, obstructions, rock excavation, temporary dewatering, etc.

The project specifications should indicate the Contractor's responsibility for providing adequate site drainage during construction. Inadequate drainage will most likely lead to disturbance of soils by construction traffic and increased volume of undercut.

This report may be made available to prospective bidders for informational purposes. We recommend that the project specifications contain the following statement:

Schnabel Engineering Consultants, Inc., has prepared this geotechnical engineering report for this project. This report is for informational purposes only and is not part of the contract documents. The opinions expressed represent the Geotechnical Engineer's interpretation of the subsurface conditions, tests, and the results of analyses conducted. Should the data contained in this report not be adequate for the Contractor's purposes, the Contractor may make, before bidding, independent exploration, tests and analyses. This report may be examined by bidders at the office of the Owner, or copies may be obtained from the Owner at nominal charge.

Additional data and reports prepared by others that could have an impact upon the Contractor's bid should also be made available to prospective bidders for informational purposes.

13.0 LIMITATIONS

We based the analyses and recommendations submitted in this report on the information revealed by our exploration. We attempted to provide for normal contingencies, but the possibility remains that unexpected conditions may be encountered during construction.

This report has been prepared to aid in the evaluation of this site and to assist in the design of the project. It is intended for use concerning this specific project. We based our recommendations on information on the site and proposed construction as described in this report. Substantial changes in loads, locations, or grades should be brought to our attention so we can modify our recommendations as needed. We would appreciate an opportunity to review the plans and specifications as they pertain to the recommendations contained in this report, and to submit our comments to you based on this review.

We have endeavored to complete the services identified herein in a manner consistent with that level of care and skill ordinarily exercised by members of the profession currently practicing in the same locality and under similar conditions as this project. No other representation, express or implied, is included or intended, and no warranty or guarantee is included or intended in this report, or other instrument of service.

FIGURES

- Figure 1: Site Vicinity Map
- Figure 2: Approximate Boring Location Plan
- Figure 3: Lateral Earth Pressure Diagram for Design of Below-Grade Walls
- Figure 4: Subdrainage Details

This Page Intentionally Left Blank



6/19/2013 This Map was created in Schnabel Engineering's Site Vicinity Map Application.

Image courtesy of USGS © 2013 Microsoft Corporation © 2010 NAVTEQ © AND
Sources: Esri, DeLorme, NAVTEQ, USGS, Intermap, iPC, NRCAN, Esri Japan, METI, Esri China
(Hong Kong), Esri (Thailand), TomTom, 2012
Projection: WGS 1984 Web Mercator Auxiliary Sphere

0 125 250 500
Feet

Scale: 1 in = 250 feet




Schnabel
ENGINEERING

8621 GEORGIA AVENUE
SILVER SPRING, MARYLAND

PROJECT NO. 12612074

SITE VICINITY
MAP

FIGURE 1



LEGEND

 APPROXIMATE SCHNABEL BORING LOCATION (2013)
B-8

1

APPROXIMATE BORING LOCATIONS (2006 & 2007)

B-1

Base Plan Provided by Macris, Hendricks & Glascock, PA dated February 2001.




8621 GEORGIA AVENUE
SILVER SPRING, MARYLAND

APPROXIMATE BORING LOCATION PLAN

PROJECT NO.: 12612074

MAY 2013

FIGURE NO.: 2



NOTES:

- 1) EARTH PRESSURE DIAGRAM SHOWN ASSUMES FULL DRAINAGE OF HYDROSTATIC PRESSURE.
- 2) SEE REPORT FOR BACKFILL MATERIAL REQUIREMENTS.



Schnabel
ENGINEERING


8621 GEORGIA AVENUE
SILVER SPRING, MARYLAND

LATERAL EARTH PRESSURE DIAGRAM
FOR DESIGN OF BELOW GRADE WALLS


PROJECT NO.: 12612074

MAY 2013

FIGURE NO.: 3




DRAINAGE DETAIL



INTERIOR FLOOR SLAB DRAINAGE DETAIL

FOUNDATION DRAIN NOTES

1. FILTER MATERIAL GRADATION SHOULD SATISFY REQUIREMENTS FOR AASHTO NO.78 COARSE AGGREGATE.
2. PERMEABLE FABRIC SHOULD HAVE EQUIVALENT OPENING SIZE NOT LARGER THAN THE NO. 70 U.S. STANDARD SIEVE SIZE.
3. SUBDRAINAGE PIPING SHOULD BE 4 INCH DIAMETER SLOTTED CORRUGATED POLYETHYLENE (P.E. TUBING) ACCORDING TO ASTM F-405 WITH MAXIMUM $\frac{1}{8}$ INCH SLOT WIDTH FOR AT LEAST THE LOWER 120° SECTOR. PIPING SHOULD BE INSTALLED TO OUTLET INTO A STORM SEWER OR SUMP WITH A PUMP.
4. WASHED GRAVEL OR CRUSHED STONE DRAINAGE BLANKET SHOULD SATISFY GRADATION REQUIREMENTS FOR AASHTO NO.57 STONE AND BE AT LEAST 4 INCH THICK.
5. APPROVED DRAINAGE PANEL SHOULD SATISFY MINIMUM THICKNESS OR FLOW CAPACITY REQUIREMENTS AS DETERMINED BY THE GEOTECHNICAL ENGINEER. GEOTEXTILE FILTER CLOTH SHOULD BE PLACED SUCH THAT IT IS IN CONTACT WITH THE SOIL BACKFILL OR EXCAVATION SHEETING.
6. BACKFILL MATERIAL TO MEET REQUIREMENTS IN PROJECT SPECIFICATIONS.
7. WEEPHOLES WHEN USED TO BE PROVIDED AT 8 FEET ON CENTER ALONG BASE OF WALL. WEEPHOLES SHALL CONSIST OF 3 INCH I.D. SOLID POLYETHYLENE PIPE.
8. DRAINGREAT™ SHALL BE USED FOR CONNECTION BETWEEN WEEPHOLE AND DRAINAGE BOARD AS SHOWN ON DETAIL. INSTALLATION TO BE DONE IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS.



ALTERNATIVE DRAINAGE DETAIL FOR SLOPED EXCAVATION

THIS PAGE IS INTENTIONALLY LEFT BLANK

APPENDIX A

SUBSURFACE EXPLORATION DATA

Subsurface Exploration Procedures
General Notes for Subsurface Exploration Logs
Identification of Soil
Boring Logs, B-1 through B-5A (2006)
Boring Logs, B-6 and B-7 (2007)
Boring Logs, B-8, B-8B and B-9 (2013)

SUBSURFACE EXPLORATION PROCEDURES

Test Borings – Hollow Stem Augers

The borings are advanced by turning an auger with a center opening of 2½ or 3¼ inches. A plug device blocks off the center opening while augers are advanced. Cuttings are brought to the surface by the auger flights. Sampling is performed through the center opening in the hollow stem auger, by standard methods, after removal of the plug. Usually, no water is introduced into the boring using this procedure.

Standard Penetration Test Results

The numbers in the Sampling Data column of the boring logs represent Standard Penetration Test (SPT) results. Each number represents the blows needed to drive a 2-inch O.D., 1¾-inch I.D. split-spoon sampler 6 inches, using a 140-pound hammer falling 30 inches. The sampler is typically driven a total of 18 or 24 inches. The first 6 inches are considered a seating interval. The total of the number of blows for the second and third 6-inch intervals is the SPT “N value.” The Standard Penetration Test is conducted according to ASTM D1586.

Soil Classification Criteria

The group symbols on the logs represent the Unified Soil Classification System Group Symbols (ASTM D2487) based on visual observation and limited laboratory testing of the samples. Criteria for visual identification of soil samples are included in this appendix. Some variation can be expected between samples visually classified and samples classified in the laboratory.

Disintegrated rock is defined as residual material with SPT N values between 60 blows per foot and refusal. Refusal is defined as an N value of 100 blows for a penetration of 2 inches or less.

Boring Locations and Elevations

Borings locations for the recent borings (2013) and the 2006 and 2007 investigations were approximately staked in the field by Schnabel personnel. Approximate boring locations are shown on Figure 2. Ground surface elevations at the boring locations have been estimated from the Macris, Hendricks & Glascock topographic drawing dated February 1, 2001. Locations and elevations should be considered no more accurate than the methods used to determine them.

GENERAL NOTES FOR SUBSURFACE EXPLORATION LOGS

1. Numbers in sampling data column next to Standard Penetration Test (SPT) symbols indicate blows required to drive a 2-inch O.D., 1 $\frac{1}{8}$ -inch I.D. sampling spoon 6 inches using a 140 pound hammer falling 30 inches. The Standard Penetration Test (SPT) N value is the number of blows required to drive the sampler 12 inches, after a 6 inch seating interval. The Standard Penetration Test is performed in general accordance with ASTM D1586.
2. Visual classification of soil is in accordance with terminology set forth in "Identification of Soil." The ASTM D2487 group symbols (e.g., CL) shown in the classification column are based on visual observations.
3. Estimated water levels indicated on the logs are only estimates from available data and may vary with precipitation, porosity of the soil, site topography, and other factors.
4. Refusal at the surface of rock, boulder, or other obstruction is defined as an SPT resistance of 100 blows for 2 inches or less of penetration.
5. The logs and related information depict subsurface conditions only at the specific locations and at the particular time when drilled or excavated. Soil conditions at other locations may differ from conditions occurring at these locations. Also, the passage of time may result in a change in the subsurface soil and water level conditions at the subsurface exploration location.
6. The stratification lines represent the approximate boundary between soil and rock types as obtained from the subsurface exploration. Some variation may also be expected vertically between samples taken. The soil profile, water level observations and penetration resistances presented on these logs have been made with reasonable care and accuracy and must be considered only an approximate representation of subsurface conditions to be encountered at the particular location.
7. Key to symbols and abbreviations:

| | | |
|--|-------------------------------|--|
| | S-1, SPT 5+10+1 | Sample No., Standard Penetration Test Number of blows in each 6-inch increment |
| | UD-1, UNDIST Rec=24", 100% | Sample No., 2" or 3" Undisturbed Tube Sample Recovery in inches, Percent Recovery |
| | SH-1, SH Rec=24", 100% | Sample No., 2" or 3" Shelby Tube Sample Recovery in inches, Percent Recovery |
| | PB-1, PB Rec=24", 100% | Sample No., 3" Pitcher Barrel Sample Recovery in inches, Percent Recovery |
| | OS-1, OS Rec=24", 100% | Sample No., 3" Osterberg Piston Sample Recovery in inches, Percent Recovery |
| | CAL-1, CAL Rec=18", 100% | Sample No., 3" Split-barrel sampler with rings Recovery in inches, Percent Recovery |

| | | |
|---|--|---|
|  | Run #1, CORE Run = 5.0 ft REC = 60", 100% RQD = 60", 100% | Core No., Rock Core Run length in feet Recovery in inches, Percent Recovery RQD in inches, Percent RQD |
|  | S-1, GEOPROBE Rec=24", 100% | Sample No., Direct Push Sample Recovery in inches, Percent Recovery |
|  | S-1, SAMPLE | Sample No., Hand Auger or Test Pit sample |

| | |
|--------------|---|
| DCP | Dynamic Cone Penetrometer |
| FID | Flame Ionization Detector Reading (ppm) |
| GP | Geostick Penetration Reading (inches) |
| LL | Liquid Limit |
| MC | Moisture Content (percent) |
| PID | Photoionization Detector Reading (ppm) |
| PL | Plastic Limit |
| PP | Pocket Penetrometer Reading (tsf) |
| TPH | Total Petroleum Hydrocarbons |
| %Passing#200 | Percent by weight passing a No. 200 Sieve |

IDENTIFICATION OF SOIL

I. DEFINITION OF SOIL GROUP NAMES (ASTM D2487)

SYMBOL GROUP NAME

| | | | | |
|---|---|--|----|------------------------------|
| Coarse-Grained Soils More than 50% retained on No. 200 sieve | Gravels – More than 50% of coarse fraction retained on No. 4 sieve Coarse, $\frac{3}{4}$ " to 3" Fine, No. 4 to $\frac{3}{4}$ " | Clean Gravels Less than 5% fines | GW | WELL GRADED GRAVEL |
| | | | GP | POORLY GRADED GRAVEL |
| | | Gravels with fines More than 12% fines | GM | SILTY GRAVEL |
| | | | GC | CLAYEY GRAVEL |
| | Sands – 50% or more of coarse Fraction passes No. 4 sieve Coarse, No. 10 to No. 4 Medium, No. 40 to No. 10 Fine, No. 200 to No. 40 | Clean Sands Less than 5% fines | SW | WELL GRADED SAND |
| | | | SP | POORLY GRADED SAND |
| | | Sands with fines More than 12% fines | SM | SILTY SAND |
| | | | SC | CLAYEY SAND |
| | Fine-Grained Soils 50% or more passes the No. 200 sieve | Silts and Clays – Liquid Limit less than 50 Low to medium plasticity | CL | LEAN CLAY |
| | | | ML | SILT |
| | | | OL | ORGANIC CLAY ORGANIC SILT |
| | | Silts and Clays – Liquid Limit 50 or more Medium to high plasticity | CH | FAT CLAY |
| | | | MH | ELASTIC SILT |
| | | | OH | ORGANIC CLAY ORGANIC SILT |
| | | | PT | PEAT |

II. DEFINITION OF SOIL COMPONENT PROPORTIONS (ASTM D2487)

Examples

| | | | |
|----------------|--------------------------|--|--------------------------------|
| Adjective Form | GRAVELLY SANDY | >30% to <50% coarse grained component in a fine-grained soil | GRAVELLY LEAN CLAY |
| | CLAYEY SILTY | >12% to <50% fine grained component in a coarse-grained soil | SILTY SAND |
| “With” | WITH GRAVEL WITH SAND | >15% to <30% coarse grained component in a fine-grained soil | FAT CLAY WITH GRAVEL |
| | WITH GRAVEL WITH SAND | >15% to <50% coarse grained component in a coarse-grained soil | POORLY GRADED GRAVEL WITH SAND |
| | WITH SILT WITH CLAY | >5% to <12% fine grained component in a coarse-grained soil | POORLY GRADED SAND WITH SILT |

III. GLOSSARY OF MISCELLANEOUS TERMS

SYMBOLS Unified Soil Classification Symbols are shown above as group symbols. A dual symbol “-“ indicates the soil belongs to two groups. A borderline symbol “/” indicates the soil belongs to two possible groups.

FILL Man-made deposit containing soil, rock and often foreign matter.

PROBABLE FILL Soils which contain no visually detected foreign matter but which are suspect with regard to origin.

DISINTEGRATED ROCK (DR) Residual materials with a standard penetration resistance (SPT) between 60 blows per foot and refusal. Refusal is defined as an SPT of 100 blows for 2" or less penetration.

PARTIALLY WEATHERED ROCK (PWR) Residual materials with a standard penetration resistance (SPT) between 100 blows per foot and refusal. Refusal is defined as an SPT of 100 blows for 2" or less penetration.

BOULDERS & COBBLES Boulders are considered rounded pieces of rock larger than 12 inches, while cobbles range from 3 to 12-inch size.

LENSES 0 to $\frac{1}{2}$ -inch seam within a material in a test pit.


LAYERS $\frac{1}{2}$ to 12-inch seam within a material in a test pit.

POCKET Discontinuous body within a material in a test pit.

MOISTURE CONDITIONS Wet, moist or dry to indicate visual appearance of specimen.


COLOR Overall color, with modifiers such as light to dark or variation in coloration.

This Page Intentionally Left Blank


Comments:

Spoon Refusal at 18.6 feet.

Boring backfilled and patched after long term water level reading.

|  TEST BORING LOG | | Project: 8651 Georgia Avenue Silver Spring, Maryland | | | | | Boring Number: Contract Number: 06120154 Sheet: 1 of 1 | | B-2 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|--|---|---|---|--|--------------------------------------|--|--|-------|------|------|---------|-------|---------|-------|-------------------|------|----------|-----|----------|-----|----------------------|------|-------|--|-----|-------|------------------|------|-----|-----|-----|-------|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|
| Boring Contractor: Recon Drilling, Inc. Boring Foreman: V. Rodas Drilling Method: 2-1/4 I.D. Hollow Stem Auger Drilling Equipment: CME 550 ATV SEA Representative: Joan Bentel Dates Started: 9/22/06 Finished: 9/22/06 Location: See Boring Location Plan Hammer Type: Automatic Ground Surface Elevation: 349.0± (feet) | | Groundwater Observations <table border="1"> <thead> <tr> <th></th> <th>Date</th> <th>Time</th> <th>Depth</th> <th>Casing</th> <th>Caved</th> </tr> </thead> <tbody> <tr> <td>Completion</td> <td>9/22</td> <td>---</td> <td>Dry</td> <td>---</td> <td>---</td> </tr> <tr> <td>Casing Pulled</td> <td>9/22</td> <td>---</td> <td>Dry</td> <td>---</td> <td>16.5'</td> </tr> <tr> <td>Long Term</td> <td>9/25</td> <td>---</td> <td>Dry</td> <td>---</td> <td>16.3'</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table> | | | | | | | | Date | Time | Depth | Casing | Caved | Completion | 9/22 | --- | Dry | --- | --- | Casing Pulled | 9/22 | --- | Dry | --- | 16.5' | Long Term | 9/25 | --- | Dry | --- | 16.3' | | | | | | | | | | | | | | | | | | | |
| | Date | Time | Depth | Casing | Caved | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Completion | 9/22 | --- | Dry | --- | --- | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Casing Pulled | 9/22 | --- | Dry | --- | 16.5' | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Long Term | 9/25 | --- | Dry | --- | 16.3' | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| DEPTH (ft) 0.5 Asphalt 1.2 Gravel 3.5 silty sand FILL, with concrete, brick and asphalt fragments, trace gravel, moist, brown and gray 9.0 silty SAND, with mica, moist, brown 13.5 silty SAND, with mica, moist, light brown and gray, trace dark brown and orangish-brown 18.6 rock fragments at 18.5 feet BOTTOM OF BORING @ 18.6 FT. | STRATA DESCRIPTION Asphalt Gravel silty sand FILL, with concrete, brick and asphalt fragments, trace gravel, moist, brown and gray silty SAND, with mica, moist, brown trace rock fragments and mica flakes, trace orangish-brown and dark brown at 6.0 feet DISINTEGRATED ROCK, trace mica, moist, brown silty SAND, with mica, moist, light brown and gray, trace dark brown and orangish-brown rock fragments at 18.5 feet BOTTOM OF BORING @ 18.6 FT. | SYMBOL FILL SM | ELEV. (ft) 348.5 347.8 345.5 340.0 335.5 330.4 | STRATUM A B C B | WL 5 10 15 20 | SAMPLING <table border="1"> <thead> <tr> <th>DEPTH</th> <th>DATA</th> </tr> </thead> <tbody> <tr> <td>9.0</td> <td>9+16+10</td> </tr> <tr> <td>7.0</td> <td>7+11+10</td> </tr> <tr> <td>5.0</td> <td>5</td> </tr> <tr> <td>4.0</td> <td>10+18+15</td> </tr> <tr> <td>3.0</td> <td>10+24+40</td> </tr> <tr> <td>2.0</td> <td>9+12+16</td> </tr> <tr> <td>1.0</td> <td>100/1</td> </tr> </tbody> </table> | | DEPTH | DATA | 9.0 | 9+16+10 | 7.0 | 7+11+10 | 5.0 | 5 | 4.0 | 10+18+15 | 3.0 | 10+24+40 | 2.0 | 9+12+16 | 1.0 | 100/1 | Unconfined Compressive Strength, tons/ft.²  N VALUE, blows/ft. 20 40 60 80 100 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | DEPTH | DATA | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | 9.0 | 9+16+10 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | 7.0 | 7+11+10 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | 5.0 | 5 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | 4.0 | 10+18+15 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | 3.0 | 10+24+40 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | 2.0 | 9+12+16 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1.0 | 100/1 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 0.5 | 9+16+10 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1.2 | 7+11+10 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 3.5 | 5 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9.0 | 10+18+15 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 13.5 | 10+24+40 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 18.6 | 9+12+16 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 100/1 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

TEST BORING LOG GAITHERSBURG BORING LOGS 06120154.GPJ SCHAEBEL.GDT 6/11/13

Comments:

Spoon Refusal at 18.6 feet.


Boring backfilled and patched after long term water level reading.



**TEST
BORING
LOG**

Project: 8651 Georgia Avenue
Silver Spring, Maryland

Boring Number: **B-3**
Contract Number: 06120154
Sheet: 1 of 2



Comments:

Spoon Refusal at 33.6 feet.
Boring backfilled and patched upon completion.

TEST
BORING
LOGProject: 8651 Georgia Avenue
Silver Spring, MarylandBoring Number: B-3
Contract Number: 06120154
Sheet: 2 of 2DISINTEGRATED ROCK, with mica,
moist, brown and gray, trace off-white
and orangish-brown (continued)

light brown and gray at 28.5 feet

33.6

gray at 33.5 feet
BOTTOM OF BORING @ 33.6 FT.

| DEPTH (ft) | STRATA DESCRIPTION | SYMBOL | ELEV. (ft) | STRA- TUM | WL | SAMPLING | Unconfined Compressive Strength, tons/ft. ² | | | |
|---------------|--------------------|--------|---------------|--------------|----|----------|--|----|----|-------|
| | | | | | | | 1 | 2 | 3 | 4 |
| | | | | | | | PL | MC | LL | 5 |
| | | | | | | | 20 | 40 | 60 | 80 |
| 33.6 | | | 313.4 | C | | 70+30/1 | | | | 100/1 |
| | | | | | | | | | | |

Comments:

Spoon Refusal at 33.6 feet.
Boring backfilled and patched upon completion.

| | | | | | | | | | | | | |
|--|---|---|-----------------------|----------------------|--|-----------------|--|--------------------|---------|----|---------|----|
|  TEST BORING LOG | | Project: 8651 Georgia Avenue Silver Spring, Maryland | | | | | Boring Number: B-4 | | | | | |
| | | | | | Contract Number: 06120154 Sheet: 1 of 1 | | | | | | | |
| Boring Contractor: Recon Drilling, Inc. | | | | | Groundwater Observations | | | | | | | |
| Boring Foreman: V. Rodas | | | | | Date | Time | Depth | Casing | Caved | | | |
| Drilling Method: 2-1/4 I.D. Hollow Stem Auger | | | | | Completion | 9/25 | --- | Dry | --- | | | |
| Drilling Equipment: CME 550 ATV | | | | | Casing Pulled | 9/25 | --- | Dry | 2.7' | | | |
| SEA Representative: Joan Bentel | | | | | | | | | | | | |
| Dates Started: 9/25/06 Finished: 9/25/06 | | | | | | | | | | | | |
| Location: See Boring Location Plan | | | | | | | | | | | | |
| Hammer Type: Automatic | | | | | | | | | | | | |
| Ground Surface Elevation: 345.0± (feet) | | | | | | | | | | | | |
| DEPTH (ft) | STRATA DESCRIPTION | SYMBOL | ELEV. (ft) | STRA- TUM | WL | SAMPLING | Unconfined Compressive Strength, tons/ft. ² | | | | | |
| | | | | | | | 1 PL | 2 | 3 MC | 4 | 5 LL | |
| 0.3 | Asphalt | FILL | 344.8 | A | | DEPTH | DATA | N VALUE, blows/ft. | | | | |
| 0.5 | Gravel | | 344.5 | | | | | 18+23+31 | 20 | 40 | 60 | 80 |
| 3.5 | silty sand FILL, with asphalt, brick, stone fragments, and wood fragments, moist, dark brown, trace black BOTTOM OF BORING @ 3.5 FT. | FILL | 341.5 | | | | 100/0 * | | | | | |

TEST BORING LOG GAITHERSBURG BORING LOGS 06120154 GPU SCHNABEL.GDT 6/1/13

Comments:

Auger and spoon refusal at 3.5 feet.

Offset boring 10 feet towards boring B-5. Refused again due to possible concrete obstructions at same elevation. Offset boring total of four times, boring cancelled.

Boring and offset borings backfilled and patched upon completion.

* = no recovery



**TEST
BORING
LOG**


Project: 8651 Georgia Avenue
Silver Spring, Maryland

Boring Number: **B-5**
Contract Number: 06120154
Sheet: 1 of 1

| Boring Contractor: Recon Drilling, Inc. | | Groundwater Observations | | | | | | | | | | | | | | | |
|---|---|--------------------------|----------------|--------------|------|----------|--|-----------------------------|---------|---------|--------------------|--|--|--|--|--|--|
| | | | | Date | Time | Depth | Casing | Caved | | | | | | | | | |
| Boring Foreman: V. Rodas | | Completion | | 9/22 | --- | Dry | --- | --- | | | | | | | | | |
| Drilling Method: 2-1/4 I.D. Hollow Stem Auger | | Casing Pulled | | 9/22 | --- | Dry | --- | 6.8' | | | | | | | | | |
| Drilling Equipment: CME 550 ATV | | | | | | | | | | | | | | | | | |
| SEA Representative: Joan Bentel | | | | | | | | | | | | | | | | | |
| Dates Started: 9/22/06 Finished: 9/22/06 | | | | | | | | | | | | | | | | | |
| Location: See Boring Location Plan | | | | | | | | | | | | | | | | | |
| Hammer Type: Automatic | | | | | | | | | | | | | | | | | |
| Ground Surface Elevation: 349.0± (feet) | | | | | | | | | | | | | | | | | |
| DEPTH (ft) | STRATA DESCRIPTION | SYMBOL | ELEV. (ft) | STRA- TUM | WL | SAMPLING | Unconfined Compressive Strength, tons/ft. ² | | | | | | | | | | |
| | | | | | | | 1 | 2 | 3 | 4 | 5 | | | | | | |
| 0.3 | Asphalt | FILL | 348.7 348.3 | A | | DEPTH | DATA | PL X | MC ◻ | LL △ | N VALUE, blows/ft. | | | | | | |
| | Gravel | | | | | | | | | | | | | | | | |
| 0.8 | sandy silt FILL, with clay pockets and wood fragments, trace brick fragments, gravel and asphalt, moist, brown, trace tan | FILL | 345.5 | A | | DEPTH | DATA | 20 40 60 80 100 | ◇ | ◆ | ◆ | | | | | | |
| | silty sand FILL, with brick, concrete and asphalt fragments, moist, tan and dark gray | | | | | | | | | | | | | | | | |
| 3.5 | 7+11+41 | | 343.0 | A | | DEPTH | DATA | PL X | MC ◻ | LL △ | N VALUE, blows/ft. | | | | | | |
| | 14+7+14 | | | | | | | | | | | | | | | | |
| 6.0 | 5 | | 343.0 | A | | DEPTH | DATA | 20 40 60 80 100 | ◇ | ◆ | ◆ | | | | | | |
| | 100/0 * | | | | | | | | | | | | | | | | |
| BOTTOM OF BORING @ 6.0 FT. | | | | | | | | | | | | | | | | | |

Comments:

Auger and spoon refusal at 6.0 feet.
Boring backfilled and patched upon completion.
* = no recovery

| | | | | | | | | | | | | |
|--|---|---|----------------------|-----------------|--|-----------------|--|---------|---------|---|---|--|
|  TEST BORING LOG | | Project: 8651 Georgia Avenue Silver Spring, Maryland | | | | | Boring Number: B-5A | | | | | |
| | | | | | Contract Number: 06120154 Sheet: 1 of 1 | | | | | | | |
| Boring Contractor: Recon Drilling, Inc. | | | | | Groundwater Observations | | | | | | | |
| Boring Foreman: V. Rodas | | | | | Date | Time | Depth | Casing | Caved | | | |
| Drilling Method: 2-1/4 I.D. Hollow Stem Auger | | | | | Completion | 9/22 | --- | Dry | --- | | | |
| Drilling Equipment: CME 550 ATV | | | | | Casing Pulled | 9/22 | --- | Dry | --- | | | |
| SEA Representative: Joan Bentel | | | | | Long Term | 9/25 | --- | Dry | --- | | | |
| Dates Started: 9/22/06 Finished: 9/22/06 | | | | | | | | | | | | |
| Location: See Boring Location Plan | | | | | | | | | | | | |
| Hammer Type: Automatic | | | | | | | | | | | | |
| Ground Surface Elevation: 349.0± (feet) | | | | | | | | | | | | |
| DEPTH (ft) | STRATA DESCRIPTION | SYMBOL | ELEV. (ft) | STRA-TUM | WL | SAMPLING | Unconfined Compressive Strength, tons/ft. ² | | | | | |
| | | | | | | | 1 PL | 2 MC | 3 LL | 4 | 5 | |
| 0.4 | Asphalt | | 348.6 | | | | | | | | | |
| 0.8 | Gravel | | 348.3 | | | | | | | | | |
| | Auger Probe | | | | | | | | | | | |
| 6.0 | silty SAND, with mica, trace rock fragments, moist, brown, trace off-white and gray trace orangish-brown at 8.5 feet | SM | 343.0 | B | | DEPTH | DATA | | | | | |
| 13.5 | DISINTEGRATED ROCK, trace mica, moist, brown ,trace off-white and orangish-brown | | 335.5 | C | | | | | | | | |
| 18.6 | gray at 18.5 feet BOTTOM OF BORING @ 18.6 FT. | | 330.4 | | | | | | | | | |
|  | | | | | | | | | | | | |

TEST BORING LOG GAITHERSBURG BORING LOGS 06120154 GPU SCHNABEL.GDT 6/1/13

Comments:

Spoon refusal at 18.6 feet.

Offset boring 10 feet towards B-2 (same elevation).

Boring backfilled and patched after long term water level reading.

Comments:

Boring backfilled and asphalt patched upon completion.
Spoon refusal at 13.6 ft.



**TEST
BORING
LOG**

Project: Additional Services at 8651 Georgia Avenue
Silver Spring, Maryland

Boring Number: **B-7**
Contract Number: 07120150
Sheet: 1 of 1

| Boring Contractor: Recon Drilling, Inc. | | Groundwater Observations | | | | | | |
|---|--|--------------------------|---------------|--------------|------|----------|--|-------|
| | | | | Date | Time | Depth | Casing | Caved |
| Boring Foreman: Nick T. | | Completion | | 9/5 | --- | Dry | --- | --- |
| Drilling Method: 2-1/4 I.D. Hollow Stem Auger | | Casing Pulled | | 9/5 | --- | Dry | --- | 7.0' |
| Drilling Equipment: CME 550 ATV | | | | | | | | |
| SEA Representative: Joan Bentel | | | | | | | | |
| Dates Started: 9/5/07 Finished: 9/5/07 | | | | | | | | |
| Location: See Boring Location Plan | | | | | | | | |
| Hammer Type: Automatic | | | | | | | | |
| Ground Surface Elevation: 343.5± (feet) | | | | | | | | |
| DEPTH (ft) | STRATA DESCRIPTION | SYMBOL | ELEV. (ft) | STRA- TUM | WL | SAMPLING | Unconfined Compressive Strength, tons/ft. ² | |
| | | | | | | | DEPTH | DATA |
| 0.3 | Asphalt | | 343.3 | | | | 20 | |
| 0.7 | Crushed Stone | | 342.8 | | | | 40 | |
| | silty sand FILL, with concrete, brick and wood fragments, moist, brown and light brown | FILL | | | | | 60 | |
| | with clay pockets, trace asphalt, dark brown at 3.5 feet | | | | | | 80 | |
| | trace foam (demolition debris) and roots at 8.5 feet | | | | | | 100 | |
| 14.0 | trace wire fragments at 13.5 feet | | 329.5 | | A | | | |
| | DISINTEGRATED ROCK, with mica, moist, grayish-brown, trace dark brown and tan | | | | | | | |
| 18.7 | BOTTOM OF BORING @ 18.7 FT. | | 324.8 | | C | | | |
| | | | | | | | | |

TEST BORING LOG GAITHERSBURG BORING LOGS 07120150 GPU SCHNABEL.GDT 5/20/13

Comments:

Boring offset three times. Encountered refusal at 8 ft at first location. Boring offset 5 ft towards B-6 (north), refusal encountered at 14 ft due to concrete obstruction. Boring offset 15 ft toward Georgia Avenue (west). Approximately the same elevation as originally staked. Boring backfilled and asphalt patched upon completion. Spoon refusal at 18.7 ft.

Schnabel
ENGINEERINGTEST
BORING
LOGProject: 8621 Georgia Avenue
Silver Spring, Maryland

B-8

Boring Number: 12612074
Contract Number: 12612074
Sheet: 1 of 1

Contractor: Recon Drilling
Leesburg, Virginia
Contractor Foreman: Chris Gudiel
Schnabel Representative: Eoin Durcan
Equipment: CME 550 ATV
Method: 2-1/4" I.D. Hollow Stem Auger

Hammer Type: Auto Hammer (140 lb)
Dates Started: 2/18/13 **Finished:** 2/18/13
Location: See Location Plan

Ground Surface Elevation: 344± (ft) Total Depth: 10.0 ft

| DEPTH (ft) | MATERIAL DESCRIPTION | SYMBOL | ELEV (ft) | STRA TUM | SAMPLING | | TESTS | REMARKS |
|---------------|--|--------|--------------|-------------|----------|------|-------|---------|
| | | | | | DEPTH | DATA | | |
| 0.2 | Asphalt | | 343.8 | | | | | |
| 0.5 | GRAVEL BASE | | 343.5 | | | | | |
| | FILL, sampled as silty sand; moist, dark brown, contains asphalt fragments, brick fragments, concrete fragments, and lean clay pockets | FILL | | | | | | |
| | Change: contains wire fragment | | | | | | | |
| 8.5 | FILL, sampled as poorly graded gravel with silt and sand; moist, brown, contains brick fragments, contains concrete | FILL | 335.5 | | | | | |
| 10.0 | | | 334.0 | | | | | |

Bottom of Boring at 10.0 ft.

Auger refusal at 10 ft (believed to have refused on construction debris, possibly old foundation or wall). Boring offset 5 ft north due to refusal in fill (Boring B-8A).

Auger refusal encountered at 10 ft in Boring B-8A (due to construction debris), boring offset a second time (see boring log B-8B for details). Borings B-8 and B-8A were backfilled upon completion and asphalt was patched.

Schnabel
ENGINEERINGTEST
BORING
LOGProject: 8621 Georgia Avenue
Silver Spring, MarylandBoring Number: B-8B
Contract Number: 12612074
Sheet: 1 of 1

| Contractor: Recon Drilling Leesburg, Virginia Contractor Foreman: Chris Gudiel Schnabel Representative: Eoin Durcan Equipment: CME 550 ATV Method: 2-1/4" I.D. Hollow Stem Auger Hammer Type: Auto Hammer (140 lb) Dates Started: 2/18/13 Finished: 2/18/13 Location: See Location Plan | Groundwater Observations | | | | | |
|---|--------------------------|------|------|-------|--------|-------|
| | | Date | Time | Depth | Casing | Caved |
| | Encountered | ▽ | 2/18 | --- | 20.0' | --- |
| | Completion | ▼ | 2/18 | --- | 19.0' | --- |
| | Casing Pulled | | 2/18 | --- | Dry | --- |
| Ground Surface Elevation: 344± (ft) Total Depth: 26.0 ft | | | | | | |

| DEPTH (ft) | MATERIAL DESCRIPTION | SYMBOL | ELEV (ft) | STRA TUM | SAMPLING DEPTH | DATA | TESTS | REMARKS |
|---------------|--|--------|--------------|-------------|-------------------|------------------------------|-------|---------|
| | Auger Probe | | | | 5 | | | |
| 13.5 | DISINTEGRATED ROCK, sampled as sandy silt; moist, light brown, estimated 5 - 10% mica | DR | 330.2 | | 10 | SS 100/2" REC=2", 100% | | |
| | Change: light brownish gray, estimated 5 - 10% rock fragments | ▽ | | | 15 | SS 100/2" REC=2", 100% | | |
| 23.5 | DISINTEGRATED ROCK, sampled as silty sand; moist, estimated 15 - 25% rock fragments | DR | 320.2 | C | 20 | SS 100/1" REC=1", 100% | | |
| 26.0 | Bottom of Boring at 26.0 ft. Auger and spoon refusal at 26 ft. Boring located 6 ft east from B-8A offset. Augered to a depth of 13.5 ft where sampling began. Boring backfilled upon completion and asphalt patched. Excess soil spoils removed from site. | | 317.7 | | 25 | SS 100/0" REC=0" | | |



Schnabel
ENGINEERING

**TEST
BORING
LOG**

Project: 8621 Georgia Avenue
Silver Spring, Maryland

Boring Number:
Contract Number: 12612074
Sheet: 1 of 2

B-9

Contractor: Recon Drilling
Leesburg, Virginia

Contractor Foreman: Chris Gudiel

Schnabel Representative: Eoin Durcan

Equipment: CME 550 ATV

Method: 2-1/4" I.D. Hollow Stem Auger

Hammer Type: Auto Hammer (140 lb)

Dates Started: 2/18/13 **Finished:**

Location: See Location Plan

Ground Surface Elevation: 346± (ft) **Total Depth:** 33.6 ft

(continued)

Schnabel
ENGINEERINGTEST
BORING
LOGProject: 8621 Georgia Avenue
Silver Spring, MarylandBoring Number: B-9
Contract Number: 12612074
Sheet: 2 of 2

| DEPTH (ft) | MATERIAL DESCRIPTION | SYMBOL | ELEV (ft) | STRA TUM | SAMPLING | | TESTS | REMARKS |
|---------------|--|--------|--------------|-------------|----------|------------------------------|-------|---------|
| | | | | | DEPTH | DATA | | |
| 33.6 | Change: estimated 30 - 45% rock fragments | DR | 312.4 | C | | SS 100/1" REC=1", 100% | | |
| | Bottom of Boring at 33.6 ft. Spoon refusal at 33.6 ft. Boring backfilled upon completion and asphalt patched. Excess soil spoils removed from site. | | | | | | | |

This Page Intentionally Left Blank

APPENDIX B

SOIL LABORATORY TEST DATA

Summary of Laboratory Tests (2006 – 1 Sheet)
Gradation Curve (2006 – 1 Sheet)

This Page Intentionally Left Blank

Contract Number: 06120154.00
Project Name: 8651 Georgia Avenue


SUMMARY OF SOIL LABORATORY TEST RESULTS

| BORING NO. | DEPTH (ft.) | STRATUM | DESCRIPTION OF SOIL SPECIMEN | SAMPLE CLASS. NO.200 | SIEVE RESULTS | | ATTERBERG LIMITS | | NATURAL MOISTURE (%) | |
|------------|-------------|---------|------------------------------|-------------------------|----------------------|-----------------------|------------------|----|----------------------|-----|
| | | | | | PERCENT PASSING NO.4 | PERCENT RETAINED NO.4 | LL | PL | PI | |
| B-1 | 6.0-7.5 | B | Silty SAND, brown | SM | 21.3 | 0.2 | NP | NP | NP | 8.4 |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |

NOTES:

1. Soil tests are in accordance with applicable ASTM standards
2. Soil classification symbols are in accordance with Unified soil classification system, based on testing indicated and visual identification.
3. Visual identification of samples is in accordance with the system used by the firm.
4. Key to abbreviation: LL = Liquid Limit; PL = Plastic Limit; PI = Plasticity Index; NP = Nonplastic

U.S. Standard Sieve Nos.



| | | |
|--------|------|--------------|
| GRAVEL | SAND | SILT OR CLAY |
|--------|------|--------------|

| Key | Sample | Depth(ft.) | Sample Description | Class. | LL | PI | Schnabel Schnabel Engineering North, LLC GRADATION CURVES | |
|-----|--------|------------|--------------------|--------|----|----|---|--|
| ■ | B-1 | 6.0-7.5 | Silty SAND, brown | SM | NP | NP | Project: 8651 Georgia Avenue | |
| | | | | | | | Contract No. 06120154.00 | |
| | | | | | | | Date: 10/04/06 Method: ASTM D422 | |